



3 Cardinal Court #592
Hilton Head, SC 29926
843-689-6500 Office
843-689-6552 Fax

Our Website: www.DecorativeConcreteUS.com

Project Installation, Descriptions and Procedures.

Attachment # A-Overlay Stamp

¼" Overlay Stamp, Color & Seal. (Approx 3-4 Days)

1. Remove furniture, plants, and cut back growing vegetation.
2. Site preparation, pressure wash, acid wash, and in some cases grind the surface.
3. Repair nonstructural cracks by grinding crack and applying an epoxy crack filler.
4. Using a polymer concrete apply a skim coat for total adhesion.
5. Apply color to the overlay concrete mix, then gauge rake, for proper thickness.
6. Using a hand trowel, and spike shoes, trowel for a smooth finish.
7. Cut in existing expansion joints.
8. Depending on the sun, wind the setting up process varies and timing is critical.
9. Apply a liquid release formula to the overlay, to allow the stamp not stick to the concrete.
10. Stamp the pattern desired.
11. Hand rub the edges for a smooth finish.
12. The next day, rub brick the expansion joints, edges, and general clean up of overlay.
13. Pressure wash entire job, wait until dry.
14. Apply accent color, wait until dry.
15. Apply Sealer, wait until dry
16. Return furniture.
17. Have customer sign off on completed job.

Expanding your patio size before overlay stamp, if required: (Approx 3-4 Days)

1. Layout area with stakes/paint (according to plans if available) for customer approval.
2. Rough grade provided by others to within a 2" tolerance and we then hand grade.
3. Form the area to be poured with 1x4's for a 4" pour.
4. Set and level all forms to provide water runoff, min 1/8" per foot, but preferably ¼" per ft.
5. Compact ground if necessary, also wet the sub surface.
6. Pour 4000 psi concrete with fiberglass for help in resisting cracks and additional strength.
7. Depending on the sun, wind the setting up process varies and timing is critical.
8. Edge the concrete with edging tool , add a 1t broom finish in preparation of overlay.

Notes to customer:

1. **IRRIGATION:** We will do our best to protect sprinkler heads. We ask that you run the irrigation so our men can mark the heads. But, bear in mind we have no idea of how your irrigation was laid out and we sometimes drive 18" stakes into the ground, and can hit the pipes delivering water to the sprinkler heads. Please contact your irrigation company to work with us and make sure all is OK before we pour. This is also a good time for you and your landscaper to plan pipes under the concrete for future needs.
2. **LANDSCAPING:** We are not landscapers, but will take care to protect shrubs and plants. But since we operate bobcats, jack hammers, shovels, axes, and men needing to work from the edge of your patio, pool deck, driveway, etc. Our work can, and sometime does damage grass etc next to the new concrete. Therefore your landscaper must replace grass, irrigation, small plant, and sometimes fill dirt.
3. **WATER LINES:** We do our best to avoid breaking water lines but sometimes it happens. If the water line is your main line we will repair it and get your water on quickly. If it is an irrigation line, please have your irrigation company perform repairs and test the system just before we pour.
4. **ELECTRIC LINES:** Electric lines for landscape lighting as well as lamp posts etc. We will do our best to protect these items, but we don't know how they where laid out, or how deep they are etc. Therefore we are not responsible for these items.

Customer : Initials _____ Date _____ Estimate # _____